



# NVblu, Inc.

14000 Thunderbolt Place, Suite E Chantilly, Virginia 20151-3225  
703.968.8888 fax 703.968.2424 www.nvblu.com

## **BASE SCOPE OF WORK AND SPECIFICATIONS**

NVblu agrees to conduct this project in accord with the follow specifications:

### **Additional Electrical Work and Additional Work in Kitchen Area (Beyond Scope of Other Remodeling Contract). Project includes the following:**

#### **Additional Kitchen Work- \$8170.00**

- Install floor tile into kitchen area (matching new floor tiling in restrooms and guard room)and, on kitchen walls, install ½” thick National Gypsum XP Board (purple board drywall),with a two-coat painted finish (matching Owner selected paint color for Guard Room)
- Install (2) Double Hung Windows in kitchen area to replace the shutter/louvers at the front of the bathhouse. Work includes trimming out and painting as necessary.

#### **Additional Electrical Work – \$8640.00**

Obtain electrical permit;

Remove existing 16 circuit electrical sub-panel in lifeguard room and replace with new 24 circuit electrical panel, to include rewiring two existing time clocks;

Supply, run, switch, assemble, and hang two ceiling fans (standard grade) in dressing rooms (one per room); and,

Wire and install (4) single pole outlets [(3) in guard room and (1) in kitchen]

- Work to include labor and materials. All finishes and fixtures are standard grade unless noted otherwise.

Any additional work required or desired will be in addition to this contract and will be billed at time and materials basis. The OWNER must specifically approve and authorize all such additional work not specifically pre-authorized within this contract. NVblu shall remove all its construction debris from site.

**Total Project Cost: \$16,810.00**